



## Mobile SRM-DX Series

These compact batching units are suitable for small scale concreting needs. The automatically operated and digitally controlled water and admixture feeding system ensures correct proportions every time along with higher operating efficiency.

Specifications	18 m <sup>3</sup> /hr	25 m <sup>3</sup> /hr
Batch capacity	500 l	750 l
Prime mover (mixer)	10 hp	15 hp
Storage and feeding system	Cross bin	Cross bin
Storage bins	4 nos.	4 nos.
Bin capacity	3.5 m <sup>3</sup> each	4 m <sup>3</sup> each
Gate control	Pneumatic gates	Pneumatic gates
Weighing method	Suspended belt conveyor system	Suspended belt conveyor system
Aggregate discharge to mixer	By aggregate weighing mixture	By aggregate weighing mixture
Water system	180 l automatic digitally controlled water feeding system	180 l automatic digitally controlled water feeding system
Admixture system	Automatic digitally controlled admixture feeding system	Automatic digitally controlled admixture feeding system
Concrete discharge height	1.6 m	1.6 m
Cement storage bin capacity and cement feeding system	0.8 m <sup>3</sup> screw conveyor type	0.8 m <sup>3</sup> screw conveyor type
Prime mover for screw conveyor	7.5 hp	3 hp
Total hp installed	35.5 hp	40.5 hp
Suggested generator capacity	50 KVA	63 KVA